STORMWATER



The FY 2010-14 Capital Improvement Program continues to address neighborhood stormwater infrastructure including Henderson Basin, Pettigru Street, and several culverts along Richland Creek.



BENNETT, MOHAWK, AND CHICK SPRINGS CROSSINGS									
Department:	PUBLIC WORKS	Ranking:	GROUP						
Status of Project:	REVISION	Start/Finish Dates:	JULY	2001	JUN	2010			
Strategic Goal:	2, 5	Project Number:	SW3377						
_									

This project will replace inadequate crossings at the following locations:

- 1. Bennett Street: Remove existing 10' x 7' culvert and replace with two 8' x 8' box culverts.
- 2. Mohawk Drive: Remove existing 11' x 7' arch pipe and replace with 24' x 8' concrete span.
- 3. Chick Springs Road: Construct one 10' x 10' box culvert adjacent to the existing two 10' x 10' box culverts.

Project Justification (Including Relationship to City Strategic Plan Goals/Objectives):

There are residential homes that flood due to the undersized crossing at Mohawk Drive, Bennett Street, and Chick Springs Road. Flooding and overtopping on Chick Springs Road during the storm events create a safety hazard and inconvenience the public.

Method for Estimating Cost:

Consultant estimate adjusted for inflation.

Project Status (As of January 1, 2009):

Design is complete.

PROJECT ITEMS	FUNDING TO-DATE	FY 09/10 COST	FY 10/11 COST	FY 11/12 COST	FY 12/13 COST	FY 13/14 COST	TOTAL PROJECT COST
Planning/Design	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Site Acquisition Costs	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Improvements	\$1,571,026	\$387,275	\$0	\$0	\$0	\$0	\$1,958,301
Equipment	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Management	\$80,850	\$0	\$0	\$0	\$0	\$0	\$80,850
TOTAL PROJECT COST	\$1,651,876	\$387,275	\$0	\$0	\$0	\$0	\$2,039,151
							TOTAL
	FUNDING TO-	FY 09/10	FY 10/11	FY 11/12	FY 12/13	FY 13/14	PROJECT
PROJECT FUNDING SOURCES (LIST)	DATE	EST. FUNDS	EST. FUNDS	EST. FUNDS	EST. FUNDS	EST. FUNDS	FUNDING
PROJECT FUNDING SOURCES (LIST) Stormwater Revenue Bond - 2001	DATE \$73,026	EST. FUNDS \$0	EST. FUNDS \$0	EST. FUNDS \$0	EST. FUNDS \$0	EST. FUNDS \$0	FUNDING \$73,026
` 7							\$73,026
Stormwater Revenue Bond - 2001	\$73,026	\$0	\$0	\$0	\$0	\$0	\$73,026
Stormwater Revenue Bond - 2001 Stormwater Fund	\$73,026 \$1,578,850	\$0 \$387,275	\$0 \$0	\$0 \$0	\$0 \$0	\$0 \$0	\$73,026 \$1,966,125
Stormwater Revenue Bond - 2001 Stormwater Fund TOTAL PROJECT FUNDING	\$73,026 \$1,578,850	\$0 \$387,275	\$0 \$0	\$0 \$0	\$0 \$0	\$0 \$0	\$73,026 \$1,966,125 \$2,039,151
Stormwater Revenue Bond - 2001 Stormwater Fund TOTAL PROJECT FUNDING OPERATIONAL COSTS	\$73,026 \$1,578,850	\$0 \$387,275 \$387,275	\$0 \$0 \$0	\$0 \$0 \$0	\$0 \$0 \$0	\$0 \$0 \$0	\$73,026 \$1,966,125 \$2,039,151
Stormwater Revenue Bond - 2001 Stormwater Fund TOTAL PROJECT FUNDING OPERATIONAL COSTS Operating Impact	\$73,026 \$1,578,850	\$0 \$387,275 \$387,275	\$0 \$0 \$0	\$0 \$0 \$0	\$0 \$0 \$0	\$0 \$0 \$0	\$73,026 \$1,966,125 \$2,039,151 \$0

HENDERSON BASIN										
Department:	PUBLIC WORKS	Ranking:	GROUP B							
Status of Project:	REVISION	Start/Finish Dates:	JULY	2007	JUN	2011				
Strategic Goal:	2, 5	Project Number:	SW339	5						

This project will replace inadequate culvert crossings at Halidon Road, Parkins Mill Road, Cleveland Street, Wembley Road, and the two crossings at Henderson Road. The Halidon Road portion of the project was funded in FY 2007-08.

Project Justification (Including Relationship to City Strategic Plan Goals/Objectives):

Presently, flooding occurs at the confluence of the main stream and Shelburne Tributary, Craigwood Court, Seabrook Court, and Wembley Drive. Erosion occurs near Fontaine Road, Craigwood Court, Stonehaven Drive on the North Stonehaven Tributary, Shelburne Road, and Carolina Avenue.

Method for Estimating Cost:

Engineering estimate adjusted for inflation.

Project Status (As of January 1, 2009):

Design is complete for the Halidon section.

PROJECT ITEMS	FUNDING TO-DATE	FY 09/10 COST	FY 10/11 COST	FY 11/12 COST	FY 12/13 COST	FY 13/14 COST	TOTAL PROJECT COST
Planning/Design	\$0	\$170,000	\$0	\$0	\$0	\$0	\$170,000
Site Acquisition Costs	\$0	\$0	\$25,000	\$0	\$0	\$0	\$25,000
Improvements	\$1,169,497	\$0	\$5,414,068	\$0	\$0	\$0	\$6,583,565
Equipment	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Management	\$0	\$0	\$320,932	\$0	\$0	\$0	\$320,932
TOTAL PROJECT COST	\$1,169,497	\$170,000	\$5,760,000	\$0	\$0	\$0	\$7,099,497
							TOTAL
	FUNDING TO-	FY 09/10	FY 10/11	FY 11/12	FY 12/13	FY 13/14	PROJECT
PROJECT FUNDING SOURCES (LIST)	DATE	EST. FUNDS	FUNDING				
Stormwater Fund	\$1,108,497	\$170,000	\$1,500,000	\$0	\$0	\$0	\$2,778,497
Sanitary Sewer Fund	\$0	\$0	\$60,000	\$0	\$0	\$0	\$60,000
Stormwater Revenue Bond - 2011	\$0	\$0	\$4,200,000	\$0	\$0	\$0	\$4,200,000
Stormwater Revenue Bond - 2001	\$61,000	\$0	\$0	\$0	\$0	\$0	\$61,000
TOTAL PROJECT FUNDING	\$1,169,497	\$170,000	\$5,760,000	\$0	\$0	\$0	\$7,099,497
OPERATIONAL COSTS							
Operating Impact		\$0	\$0	\$0	\$0	\$0	\$0
Cumulative Operating Impact		\$0	\$0	\$0	\$0	\$0	\$0
FTEs Added		0.00	0.00	0.00	0.00	0.00	0.00
Cumulative FTEs Added		0.00	0.00	0.00	0.00	0.00	0.00

PINEHURST AND WINDSOR CROSSINGS											
PUBLIC WORKS	Ranking:	GROUP C									
PLANNED/PROGRAMMED	Start/Finish Dates:	JULY	2005	JUN	2012						
2 ,5	Project Number:	SW3401									
	PUBLIC WORKS PLANNED/PROGRAMMED	PUBLIC WORKSRanking:PLANNED/PROGRAMMEDStart/Finish Dates:	PUBLIC WORKSRanking:GROUP OF THE PROGRAMMEDPLANNED/PROGRAMMEDStart/Finish Dates:JULY	PUBLIC WORKSRanking:GROUP CPLANNED/PROGRAMMEDStart/Finish Dates:JULY 2005	PUBLIC WORKSRanking:GROUP CPLANNED/PROGRAMMEDStart/Finish Dates:JULY 2005JUN						

This project will replace undersized culvert crossings at Pinehurst Drive and Windsor Drive. Due to upstream development, the existing culvert size became insufficient to handle the increasing stormwater flow. To mitigate this, the project will install a new arch 10' x 5.5' x 80' culvert at Pinehurst Drive and a new arch 12' x 5.5' x 80' at Windsor Drive.

Project Justification (Including Relationship to City Strategic Plan Goals/Objectives):

This project will reduce flooding in the area, prevent road overtopping, and improve the creek bank's stability. The Richland Creek tributary which crosses under Pinehurst Drive and Windsor Drive carries flow from approximately 350 acres. The existing culverts have minimal capacity to carry heavy storm flows in the creek and are prone to blockage.

The proposed upgrades will significally improve the hydraulic capacity at the crossing, reduce regular maintenance, and benefit private property owners directly upstream from a significant reduction in the backwater flood profile.

Method for Estimating Cost:

Estimates based on projects of similar size and scope.

Project Status (As of January 1, 2009):

Funding is scheduled to begin in FY 2010-11.

PROJECT ITEMS	FUNDING TO-DATE	FY 09/10 COST	FY 10/11 COST	FY 11/12 COST	FY 12/13 COST	FY 13/14 COST	TOTAL PROJECT COST
Planning/Design	\$0	\$0	\$40,000	\$0	\$0	\$0	\$40,000
Site Acquisition Costs	\$0	\$0	\$0	\$30,000	\$0	\$0	\$30,000
Improvements	\$0	\$0	\$0	\$1,200,000	\$0	\$0	\$1,200,000
Equipment	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Management	\$0	\$0	\$0	\$60,000	\$0	\$0	\$60,000
TOTAL PROJECT COST	\$0	\$0	\$40,000	\$1,290,000	\$0	\$0	\$1,330,000
							TOTAL
	FUNDING TO-	FY 09/10	FY 10/11	FY 11/12	FY 12/13	FY 13/14	PROJECT
PROJECT FUNDING SOURCES (LIST)	DATE	EST. FUNDS	FUNDING				
Stormwater Fund	\$0	\$0	\$40,000	\$1,290,000	\$0	\$0	\$1,330,000
TOTAL PROJECT FUNDING	\$0	\$0	\$40,000	\$1,290,000	\$0	\$0	\$1,330,000
OPERATIONAL COSTS							
Operating Impact		\$0	\$0	\$0	\$0	\$0	\$0
Cumulative Operating Impact		\$0	\$0	\$0	\$0	\$0	\$0
FTEs Added		0.00	0.00	0.00	0.00	0.00	0.00
Cumulative FTEs Added		0.00	0.00	0.00	0.00	0.00	0.00

WESTVIEW AVENUE										
Department:	PUBLIC WORKS	Ranking:	GROUP B							
Status of Project:	REVISION	Start/Finish Dates:	JULY	2002	JUN	2010				
Strategic Goal:	2, 5	Project Number:	SW3394							

This project will replace an inadequate crossing at Westview Avenue by installing a new 15' x 5.5' x 80' arch culvert.

Project Justification (Including Relationship to City Strategic Plan Goals/Objectives):

The existing culvert under Westview Avenue is inadequate to handle the stormwater runoff during heavy storms. Residential properties along Westview experience flooding because water backs up at the crossing.

Method for Estimating Cost:

Consultant estimate adjusted for inflation.

Project Status (As of January 1, 2009):

Design must be updated.

PROJECT ITEMS	FUNDING TO-DATE	FY 09/10 COST	FY 10/11 COST	FY 11/12 COST	FY 12/13 COST	FY 13/14 COST	TOTAL PROJECT COST
Planning/Design	\$3,200	\$0	\$0	\$0	\$0	\$0	\$3,200
Site Acquisition Costs	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Improvements	\$374,500	\$216,571	\$0	\$0	\$0	\$0	\$591,071
Equipment	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Management	\$18,725	\$10,829	\$0	\$0	\$0	\$0	\$29,554
TOTAL PROJECT COST	\$396,425	\$227,400	\$0	\$0	\$0	\$0	\$623,825
PROJECT FUNDING SOURCES (LIST)	FUNDING TO- DATE	FY 09/10 EST. FUNDS	FY 10/11 EST. FUNDS	FY 11/12 EST. FUNDS	FY 12/13 EST. FUNDS	FY 13/14 EST. FUNDS	TOTAL PROJECT FUNDING
Stormwater Fund	\$393,280	\$227,400	\$0	\$0	\$0	\$0	\$620,680
Stormwater Revenue Bond - 2001	\$3,145	\$0	\$0	\$0	\$0	\$0	\$3,145
TOTAL PROJECT FUNDING	\$396,425	\$227,400	\$0	\$0	\$0	\$0	\$623,825
OPERATIONAL COSTS		ФО.	r _O	C O	ФО.	\$0	# 0
Operating Impact		\$0	\$0	\$0	\$0	\$0	\$0
Cumulative Operating Impact		\$0	\$0	\$0	\$0	\$0	\$0
FTEs Added		0.00	0.00	0.00	0.00	0.00	-
Cumulative FTEs Added		0.00	0.00	0.00	0.00	0.00	0.00

PETTIGRU STREET IMPROVEMENTS											
IBLIC WORKS	Ranking:	GROUP B									
ANNED/PROGRAMMED	Start/Finish Dates:	JULY	2011	JUN	2012						
5	Project Number:	TBD									
.,	ANNED/PROGRAMMED	ANNED/PROGRAMMED Start/Finish Dates:	ANNED/PROGRAMMED Start/Finish Dates: JULY	ANNED/PROGRAMMED Start/Finish Dates: JULY 2011	ANNED/PROGRAMMED Start/Finish Dates: JULY 2011 JUN						

This project upgrades stormwater infrastructure on Pettigru Street. This project involves the addition of approximately 850 feet of new stormwater pipe and associated inlet structures. Also included is the replacement of approximately 300 feet of sanitary sewer main and one manhole. Curb, gutter, and pavement are to be upgraded in the affected area and coordinate with SCDOT activities at the end of Pettigru to improve traffic and parking. Additionally, the eroded bank along Richland Creek needs to be stabilized.

Project Justification (Including Relationship to City Strategic Plan Goals/Objectives):

This project is located in the Historic Pettigru District that abuts Cleveland Park and Richland Creek. The Pettigru District has been developed into a light business district, and the associated business parking area has caused a concentration of stormwater runoff that channels into the project area overrunning the existing infrastructure. Additionally, stormwater flow from this area into Cleveland Park and Richland Creek is causing significant erosion problems. In order to affect a permanent solution to the above issues, the stormwater runoff needs to be captured and diverted to existing storm water infrastructure at the end of Pettigru Street and minimize runoff through the Upstate Woodland Garden and Cleveland Park.

Method for Estimating Cost:

Informal engineering estimate adjusted for inflation in future years.

Project Status (As of January 1, 2009):

Preliminary designs have been completed that outline the scope of this project.

		_				_	TOTAL
		FY 09/10	FY 10/11	FY 11/12	FY 12/13	FY 13/14	PROJECT
PROJECT ITEMS	FUNDING TO-DATE	COST	COST	COST	COST	COST	COST
Planning/Design	\$0	\$0	\$0	\$0	\$0	\$0	
Site Acquisition Costs	\$0	\$0	\$0	\$45,000	\$0	\$0	\$45,000
Improvements	\$0	\$0	\$0	\$334,250	\$0	\$0	\$334,250
Equipment	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Management	\$0	\$0	\$0	\$16,713	\$0	\$0	\$16,713
TOTAL PROJECT COST	\$0	\$0	\$0	\$395,963	\$0	\$0	\$395,963
							TOTAL
	FUNDING TO-	FY 09/10	FY 10/11	FY 11/12	FY 12/13	FY 13/14	PROJECT
PROJECT FUNDING SOURCES (LIST)	DATE	EST. FUNDS	FUNDING				
Stormwater Fund	\$0	\$0	\$0	\$317,213	\$0	\$0	\$317,213
Sanitary Sewer Fund	\$0	\$0	\$0	\$78,750	\$0	\$0	\$78,750
TOTAL PROJECT FUNDING	\$0	\$0	\$0	\$395,963	\$0	\$0	\$395,963
OPERATIONAL COSTS							
Operating Impact		\$0	\$0	\$0	\$0	\$0	\$0
Cumulative Operating Impact		\$0	\$0	\$0	\$0	\$0	\$0
FTEs Added		0.00	0.00	0.00	0.00	0.00	0.00
Cumulative FTEs Added		0.00	0.00	0.00	0.00	0.00	0.00

